



IRRIGATION
TRAINING &
RESEARCH
CENTER

Flathead Indian Irrigation Project *Overview*



**Bureau of Indian Affairs Division of Water and Power
Flathead Indian Irrigation Project
*St. Ignatius, Montana***

April 2016

**IRRIGATION
TRAINING &
RESEARCH
CENTER**

Prepared by

Irrigation Training & Research Center (ITRC)
California Polytechnic State University
San Luis Obispo, CA 93407-0730
805-756-2379
www.itrc.org

Prepared for

Dave Fisher, M.S., P.E. Agricultural Engineer
Chief, Branch of Irrigation and Power
Division of Water and Power
Bureau of Indian Affairs Office of Trust Services
13922 Denver West Parkway, Suite 300
Lakewood, CO 80401
david.fisher@bia.gov
303-231-5225 office
303-929-7622 cell

Disclaimer:

Reference to any specific process, product or service by manufacturer, trade name, trademark or otherwise does not necessarily imply endorsement or recommendation of use by either California Polytechnic State University, the Irrigation Training & Research Center, or any other party mentioned in this document. No party makes any warranty, express or implied and assumes no legal liability or responsibility for the accuracy or completeness of any apparatus, product, process or data described previously. This report was prepared by ITRC as an account of work done to date. All designs are conceptual, and cost estimates are subject to final confirmation.

Irrigation Training & Research Center
April 2016

TABLE OF CONTENTS

Overview

Camas Canal Unit Modernization

- Improvements at Hubbard Reservoir and Head of Camas A Canal
- Operation near Upper Dry Fork Creek Reservoir
- Control near the Lower Dry Fork Reservoir
- Southern End of the Valley
- Improved Water Level Control along the Camas Main Canals

Placid Canal and Jocko River Modernization

- Placid Canal Improvements
- Upper and Lower Jocko Reservoir Improvements
- Tabor Feeder Canal Improvements

Jocko Canal Unit Modernization

- K Canal Unit
- S Canal Unit
- S and J Canal Reservoir
- E Canal Modifications
- Canal and Lateral Water Level Control Improvements
- Limited-Demand Pipelines

Lower J and Revais Canal Modernization

- Head of Lower J Canal
- Revais Pump Improvements
- Improved Water Level Control

Mission Canal Unit Modernization

- Tabor Reservoir
- Dry Creek Pool
- Mission Reservoir Discharge
- Mission A Canal at Ashley Creek
- Modernization Changes to Mission B Canal
- Mission Area Piping
- Improvements to Mission F Canal

Mission H Canal Modernization

- Mission Creek Pump
- Lower Mission H Pump

Crow Creeks, Kicking Horse, and Ninepipe Reservoir Modernization

- Pablo Feeder Canal at Post and Three Crow Creek Crossings
- Control Improvements near Kicking Horse Reservoir
- Control Improvements near Ninepipe Reservoir

Post Canal Unit Modernization

- Post C Canal and Lateral 25C Subsystem
- Post F Canal Superhighway
- Improved Water Level Control along Post D Canal
- Flow Measurement to Hillside Reservoir

Moiese Canal System Modernization

- New Operational Management Scheme
- Hillside Pipeline
- Improvements along the MA Canal
- Level Pool System
- Limited-Demand Pipelines

Pablo Feeder Canal Modernization near Polson

- Improvements at Flathead River Pumps
- Pablo Feeder Canal Pumpback System
- Polson Pipelines
- Improved Flow Measurement at Head of Pablo A Canal
- Improvements to Mud Creek and Ronan B Canal

Valley View Modernization

- Control Improvements near the Valley View Tunnel
- Sub-Lateral 31A-1 Restart and Spill
- Lateral 31A Regulating Reservoir
- Improved Water Level Control along Lateral 31A
- Sub-Lateral 31A-0.6 Limited-Demand Pipeline
- Improvements along Sub-Lateral 31A-0.7 and 31A-1

Modernization near Horte Reservoir

- Pablo A Canal and Horte Reservoir Pumpback System
- Round Butte Road Interceptor and Horte Reservoir Flowback Pipeline System
- Improvements to Upper Portion of Lateral 70A
- West Pablo Interceptor Pipeline

SCADA

- Proposed SCADA Sites
- SCADA Architecture
- Communications
- Roadmap
- Shared SCADA Sites
- Estimated Costs
- General SCADA Overview

On-Farm Irrigation

- Side Roll Sprinkler Systems
- Center Pivot Systems
- The Solution

Appendices

- Appendix A: Flow Measurement
- Appendix B: AS2000 Trash Screens